

Hossein Derakhshan, Dmytro Dizhur, Michael C. Griffith, and Jason M. Ingham
In situ out-of-plane testing of as-built and retrofitted unreinforced masonry walls
Journal of Structural Engineering, 2014; 140(6):04014022-1-04014022-12

© 2014 American Society of Civil Engineers.

Published at: [http://dx.doi.org/10.1061/\(ASCE\)ST.1943-541X.0000960](http://dx.doi.org/10.1061/(ASCE)ST.1943-541X.0000960)

PERMISSIONS

<http://ascelibrary.org/page/informationforasceauthorsreusingyourownmaterial>

Draft Manuscript

Authors may post the final draft of their work on open, unrestricted Internet sites or deposit it in an institutional repository when the draft contains a link to the bibliographic record of the published version in the [ASCE Library](#) or [Civil Engineering Database](#). "Final draft" means the version submitted to ASCE after peer review and prior to copyediting or other ASCE production activities; it does not include the copyedited version, the page proof, or a PDF of the published version.

1 December 2016

<http://hdl.handle.net/2440/91068>

1 Title: In-situ out-of-plane testing of as-built and retrofitted unreinforced masonry walls
2 Hossein Derakhshan¹, Dmytro Dizhur², Michael C. Griffith³, and Jason M. Ingham⁴, M.ASCE

3 ABSTRACT

4 The out-of-plane behavior of as-built and retrofitted unreinforced masonry (URM) walls was
5 investigated by conducting in-situ static airbag tests in four buildings. The age of the buildings
6 varied from 80 to 130 years, and all but one were constructed using clay brick masonry with
7 timber floor and roof diaphragms. The fourth building was a reinforced concrete frame structure
8 with pre-cracked clay block partition walls in addition to partition walls that appeared
9 undamaged. The test program was comprised of testing five one-way vertically spanning solid
10 URM walls from the group of three URM buildings and testing four two-way spanning URM
11 partition walls from the reinforced concrete frame building. All walls were tested with their
12 original support conditions, but three one-way spanning walls were additionally re-tested with
13 modified support conditions. These additional tests allowed the effects of wall support type to be
14 investigated, including the influence of a concrete ring beam used at the floor levels and the
15 influence of wall to timber diaphragm anchorage by means of grouted steel rods. Several walls
16 were next retrofitted by adding either near-surface mounted (NSM) carbon fiber reinforced
17 polymer (FRP) strips or NSM twisted steel bars (TSB), and were then re-tested. A comparison

1 Post-doctoral Research Fellow, School of Civil, Environmental, and Mining Engineering, The University of Adelaide, SA 5005, Australia, hossein.derakhshan@adelaide.edu.au

2 Post-doctoral Research Fellow, Department of Civil & Environmental Engineering, University of Auckland, Private Bag 92019, Auckland 1010, New Zealand, ddiz001@aucklanduni.ac.nz

³ Professor, School of Civil, Environmental, and Mining Engineering, University of Adelaide, SA 5005, Australia, mcgrif@civeng.adelaide.edu.au

⁴ Professor, Department of Civil & Environmental Engineering, University of Auckland, Private Bag 92019, Auckland 1010, New Zealand, j.ingham@auckland.ac.nz

18 between the results of the tests on as-built walls and the tests conducted on retrofitted walls
19 suggests that the simple retrofit techniques that were used are suitable for URM wall
20 strengthening to ultimate limit state (ULS) design. The test results in two buildings highlighted
21 significant inherent variability in masonry material properties and construction quality, and
22 recommendations were made for the seismic assessment and retrofit of URM walls. An
23 analytical trilinear elastic model especially useful when assessing the dynamic stability of
24 cracked one-way spanning walls proved to satisfactorily predict the maximum wall strength,
25 excluding those walls that developed arching action.

26 **CE Database subject headings:** Brick masonry; Walls; In situ tests; Flexural strength; Lateral
27 loads; Axial loads; Stiffness
28

29 INTRODUCTION

30 While laboratory testing is suitable for a parametric wall behavior study, in-situ testing provides
31 an opportunity to study real wall behavior in existing buildings, including the effects of actual
32 wall support conditions. In-situ testing has also been recommended in section C7.2.3.3.4 of
33 ASCE (2007) as an alternative method for out-of-plane URM wall seismic assessment. Calvi et
34 al. (1996) noted that structural masonry assessment practice should be evaluated by testing, and
35 because the construction of exact replicas of historic unreinforced masonry bearing walls is
36 impractical, in-situ testing is frequently the most viable experimental option. Despite this notion,
37 in-situ out-of-plane tests on full-scale URM walls have not commonly been conducted, and most
38 available literature reports experimental programs that consist of in-situ testing for material
39 characteristics (Corradi et al. 2003; Chiostriini et al. 2003) or non-destructive testing of masonry
40 structures or sub-assemblies (Lopes et al. 2009; Carpinteri et al. 2005). A third approach that

41 retains the existing masonry materials and construction quality but disrupts the support
42 conditions and existing stress states has been to extract masonry wall panels and transport them
43 to testing facilities (Abrams et al. 1996).

44

45 The flexural response of URM walls can be improved by using near-surface-mounted carbon
46 fibre-reinforced-polymer (NSM FRP) strips (Griffith et al. 2013). Different wall failure modes
47 associated with this retrofit technique have been discussed in Hamed and Rabinovitch (2010),
48 and further studies focused on the characterization of FRP debonding as the preferred failure
49 mode have been reported in Kashyap et al. (2012) and the references therein. In the composite
50 NSM FRP retrofitted wall section, the FRP strips resist the tensile stresses and the masonry
51 material resists the compression stresses. Due to the cyclic nature of the earthquake forces, the
52 strips should therefore be inserted on both wall surfaces.

53

54 Included within this research program were walls having grouted vertical steel anchor bars (SA;
55 Fig. 1) regularly spaced along the top edge, and a wall having a concrete ring beam (CB) placed
56 along the top edge. The provision of steel anchor bars at the wall top edge has often been
57 included as part of URM building retrofit projects, with the purpose being to promote wall
58 deformations in a simply-supported mode as opposed to a cantilever mode. The presence of a
59 concrete ring beam at building floor levels promotes arching actions that improve the wall out-
60 of-plane behavior. As opposed to confined masonry wall construction, the wall tested with a CB
61 support type in this research program had no vertical concrete ties.

62

63 This research program also includes walls retrofitted using either NSM FRP strips or using NSM
64 twisted steel bars (NSM TSB). The effectiveness of the retrofit work undertaken on the tested
65 walls is evaluated by discussing the failure modes and improvements in the wall strength and
66 ductility.

67

68 A system of airbags were used to subject the test walls to uniform out-of-plane forces, which
69 Priestley (1985) suggested to be a realistic representation of the out-of-plane seismic forces
70 applied to URM walls. Details of this field study are reported, comparison is made between the
71 predicted and measured strengths of the as-built walls, and comparison is also made between the
72 measured strength values of the as-built and retrofitted walls. Finally, the effectiveness of the
73 retrofit schemes is discussed.

74

75 ANALYTICAL MODEL

76 The two-way bending tests were conducted to proof-test wall capacity following a procedure
77 recommended in section C7.2.3.3.4 of ASCE (2007). As recommended in that reference, the
78 applied forces were limited to the level required by the seismic loading code and in all cases
79 were insufficient to induce wall failure. Similarly, one of the one-way vertically spanning walls
80 was subject to significant arching action, and the limited capacity of the in-situ test setup
81 prevented that wall from cracking. Therefore the accuracy of relevant predictive models, e.g.
82 Vaculik (2012) for two-way bending walls and Abrams et al. (1996) for arching action, could not
83 be verified using the results from this in-situ test program.

84

85 The tested one-way vertically spanning URM walls had no vertical restraint to facilitate the
 86 development of arching action, and consequently the measured response of these walls was
 87 compared against a model proposed by Derakhshan et al. (2013) and another similar alternative
 88 (Fig. 2). The strength of this type of wall is relatively low and was within the capacity of the
 89 adopted test setup, such that model verification was possible for this group of walls. As
 90 discussed at the end of this section, the trilinear model is especially useful when assessing the
 91 out-of-plane dynamic stability of URM walls that have slenderness ratios exceeding values
 92 recommended in Table 7-5 of ASCE (2007). Abrams et al. (1996) proposed a model for walls
 93 that are subject to arching action from surrounding frame elements and suggested that these walls
 94 typically satisfy seismic force demand, even for regions of high seismicity. Therefore the
 95 dynamic stability of cracked walls subject to arching action is rarely required to be checked, as
 96 these walls generally satisfy strength requirements.

97

98 Using the cracked wall free body diagram and assuming rigid rocking response the theoretical
 99 wall maximum lateral resistance and instability displacement were obtained as:

$$100 \quad \hat{w}_0 = \frac{Wt}{(\beta - \beta^2)h^2} [2(1 - \beta) + \psi(2 - \beta)] \quad (1)$$

101 and

$$102 \quad \hat{\Delta}_{ms} = t \frac{1 + \psi \left(\frac{1 - 0.5\beta}{1 - \beta} \right)}{1 + \frac{\psi}{1 - \beta}} \quad (2)$$

103 where t , h , and β are, respectively, the wall effective thickness, total wall height, and the ratio of

104 the height of the lower wall segment to the total wall height. When determining the effective
 105 wall thickness, the depth of mortar pointing and the thickness of weak plaster (as discussed later)
 106 should be excluded. W and ψ are respectively the wall weight per mm length and the ratio of
 107 applied overburden to wall weight. \hat{W}_0 and $\hat{\Delta}_{ms}$ are, respectively, the predicted wall lateral
 108 resistance and the instability displacement assuming rigid rocking as required for the rigid
 109 bilinear model shown in Fig. 2.

110
 111 The ratio of the actual wall maximum lateral resistance to the theoretical equivalent value (Eq. 1)
 112 was defined as the *percentage of maximum rigid resistance (PMR)*. The formulae were next
 113 calibrated based on laboratory airbag testing of full-scale walls, and it was found that:

$$114 \quad PMR_{emp}(\%) = 83 - \frac{0.0016h}{f'_j} \left(\psi + \frac{(1-\beta)(2\psi + 2 - \beta)}{2(1-\beta) + (2-\beta)\psi} \right) \frac{t_n}{t} \quad (3)$$

115 where, f'_j and t_n are, respectively, the mortar compressive strength and wall nominal thickness.

116
 117 The predicted maximum wall actual lateral resistance, W_{max} (Fig. 2), is calculated as the product
 118 of the PMR_{emp} ratio from Eq. 3 and \hat{W}_0 from Eq. 1. The wall lateral resistance corresponding to
 119 the plateau in an idealized trilinear model (Doherty 2000), w_i , was approximated in Derakhshan
 120 et al. (2013) as being 90% of the predicted maximum wall resistance, W_{max} , and therefore,

$$121 \quad w_i = 0.9PMR_{emp}\hat{W}_0 \quad (4)$$

122 Similarly, simplified equations were proposed in Derakhshan et al. (2013) to calculate the

123 predicted wall instability, Δ_{ins} , using $\hat{\Delta}_{ins}$. The trilinear model can be obtained using coordinates

124 $(0,0)$, (Δ_1, w_i) , (Δ_2, w_i) , and $(\Delta_{ins}, 0)$, with the two intermediate wall displacements being defined

125 as:

$$126 \quad \Delta_1 = 0.04\Delta_{ins} \quad (5)$$

127 and

$$128 \quad \Delta_2 = (1 - 0.009PMR_{emp})\Delta_{ins} \quad (6)$$

129 Using time-history analyses, Griffith et al. (2003) showed that the initial stiffness of cracked out-

130 of-plane loaded walls (i.e. w_i / Δ_1) is not a significant influencing factor when walls are assessed

131 for dynamic stability. The acceptance criterion in these procedures (e.g. ASCE 2007, NZSEE

132 2006) is typically that the cracked wall displacement should not exceed 50%-60% of the wall

133 instability displacement, Δ_{ins} . As the ratio of Δ_{ins} to Δ_1 is substantial for a cracked URM wall,

134 the wall response can be predicted if w_i and Δ_2 in the trilinear models are reasonably accurate.

135 Once the trilinear model has been developed, the wall displacement response can be calculated

136 using a response spectrum method and assuming an equivalent linear system having a secant

137 stiffness corresponding to point (Δ_2, w_i) .

138 **GENERAL DETAILS OF THE CASE STUDY BUILDINGS**

139 The test program included three buildings with load-bearing URM walls, namely Avon House

140 (AH; Fig. 3a; built 1884), Allen's Trade Complex (AT; Fig. 3b; built 1911), and Wintec F Block

141 (WT; Fig. 3c; built 1917). These three buildings were constructed using clay bricks and timber

142 floor and roof diaphragms. The testing performed in these buildings was limited to one-way
143 vertically spanning walls. The Allen's Trade Complex building had been previously damaged in
144 the December 2007 M6.8 Gisborne earthquake, but no visible damage was found in the tested
145 wall. Both the Avon House building and the Wintec F Block appeared undamaged prior to
146 testing, although the former was located in a region (Wellington, New Zealand) that is subject to
147 high winds and high seismicity.

148

149 Tests were also conducted on single-wythe unreinforced terracotta hollow block masonry
150 partition walls of the three-storey William Weir House (WH; Fig. 3d; built 1932), which had a
151 reinforced concrete frame with concrete floor slabs and a timber roof. These tests were
152 conducted with the walls loaded in a two-way bending condition and included two apparently
153 undamaged walls and two pre-cracked partition walls. The building is located in a highly seismic
154 region of New Zealand (Wellington), and had been subject to prior earthquakes. The 24 June
155 1942 Wairarapa earthquake (M7.2, Modified Mercalli in Wellington: 6 to 7 depending on ground
156 structure) and the 02 August 1942 Wairarapa earthquake (M7, Modified Mercalli in
157 Wellington: 6) occurred 10 years after the building had been constructed, with widespread
158 collapse of chimneys, masonry walls and parapets into Wellington streets being reported
159 (Downes et al. 2001). It is assumed that the cracked walls in WH was attributable to prior
160 earthquake loading as these cracked walls had no support along their top edge and were located
161 in the top-storey. It is also possible that even the second-storey walls had some internal cracking
162 that was not visible.

163 **WALL PROPERTIES**

164 All test walls were either single-wythe or double-wythe (see Fig. 4) and had plaster finish on one
165 or both faces as detailed in Table 1. Walls in Avon House had lime-based plaster with added
166 horse hair (Fig. 4a) with an average thickness of 20 mm, and walls in the other test buildings had
167 10-15 mm thick cement-based plaster. As an exception, Wall AH3 had undergone a prior seismic
168 upgrade by means of an applied layer of high cement content plaster on one surface, with the
169 other wall face having the original lime-based plaster finish.

170

171 Walls subjected to one-way bending were prepared by introducing two vertical wet cuts using a
172 concrete chainsaw, resulting in an isolated wall strip that permitted out-of-plane rocking. The
173 final length of one-way vertically spanning walls was recorded as varying between 1170 mm and
174 1250 mm, as detailed in Table 1 and Fig. 5. Most walls spanned the height of a complete storey,
175 with the exceptions being AH3 and AT. Tests were performed only on the lower parts of these
176 walls, so that the top wall segments could be retained for the reasons explained below. AT was a
177 lower central segment of an end gable (crown height 6500 mm from the first level timber floor,
178 see also Fig. 3b), and the building owner wished to retain the gable end and to demolish the end
179 wall to only the eaves level. The aforementioned vertical cuts were therefore made up to a height
180 of 3000 mm from the timber floor, forming a continuous top support (C, Fig. 5e). This
181 configuration resulted in the wall having an applied overburden load that was equal to the weight
182 of the masonry column above the wall, which was calculated as 13 kN per meter length of wall.
183 Wall AH3 was to be demolished only up to a height of 2700 mm from the wall base (storey
184 height 3100 mm) to allow preservation of the original roof drainage details as requested by the
185 owner. Therefore the test area was isolated from the rest of the wall by forming a lintel assembly

186 that accommodated up to 25 mm vertical movement at the wall top (Fig. 5d). It was intended that
187 wall vertical movements due to out-of-plane rocking be limited to 25 mm to exclude potential
188 damage to higher elevation brickwork.

189

190 AH1 and AH2 were two similar test strips of a single partition wall, with steel plates embedded
191 in three of the mortar joints of the wall (see Fig. 4a). The severely corroded plates were
192 considered to not increase wall strength for the one-way bending condition.

193

194 The top horizontal edges of WH1 and WH2 was unrestrained, but the other edges were supported
195 by either a reinforced concrete structural element or a URM flange wall (Fig. 6). These walls had
196 cracks that were less than 1 mm open, but the cracking extended through the entire wall
197 thickness. The existing cracking in Wall WH1 was less extensive than that shown for WH2 in
198 Fig. 6 and was limited to three vertical cracks at middle-top of the wall and a minor diagonal
199 crack at one base corner. Unlike WH1 and WH2, partition Walls WH3 and WH4 were restrained
200 by a concrete beam along the top horizontal edge. Due to identical dimensions and proximity,
201 Wall WH3 and Wall WH4 were assumed identical and tested in, respectively, the as-built and
202 NSM FRP retrofitted condition. As discussed later, the results from testing suggested significant
203 differences in the wall construction, e.g. thickness of plaster on the wall face subject to tension,
204 or different levels of non-visible wall damage that prevented the effectiveness of the retrofit
205 scheme to be measured.

206 **Masonry pattern**

207 The single-wythe walls had been built using a running bond, and the double-wythe walls had
208 been constructed using a common bond pattern with header bricks located every fourth course.
209 The double-wythe walls of AH building (Wall AH3) had only a few header bricks (Fig. 7a) and
210 although the wall appeared to function as a single solid wall during the airbag tests, it separated
211 into two wythes (Fig. 7b) during the ensuing demolition. This separation of wall wythes was
212 attributed to the lack of binding header courses.

213 **MATERIAL PROPERTIES**

214 Material properties were determined by conducting in-situ and laboratory tests on extracted
215 samples, with the results summarised in Table 2. The masonry density was calculated in the
216 laboratory as 1650 kg/m^3 for the partition walls of building WH, and as 1800 kg/m^3 on average
217 for all other walls. Masonry prism testing for building WH was conducted in the laboratory on
218 two-block high prisms measuring approximately $330 \text{ mm} \times 300 \text{ mm} \times 95 \text{ mm}$ (Fig. 8a), but
219 masonry testing for the URM bearing wall buildings was conducted on three-brick high prisms.
220 The plaster layer was removed from the samples prior to prism testing.

221
222 The masonry flexural bond strength (f'_{fb}) for building WH was derived from four point bending
223 tests performed in the laboratory on masonry beam samples that included the plaster layer
224 (Fig. 8b), but the strength value reported for building AH was determined on site following
225 ASTM 1072 – 00a (ASTM 2001) after removing the plaster layer. As 50 mm mortar cube
226 samples required for mortar testing using the procedure recommended in ASTM C780-02
227 (ASTM 2002) are unattainable from actual buildings, irregular mortar samples were cut into
228 measurable cubic shapes and tested in compression. The average length, width and height of

229 plaster samples for building WH were 26 mm, 21 mm and 26 mm respectively. The mortar
230 samples from building WT measured on average 36 mm long \times 24 mm wide \times 30 mm high with
231 little variation, and similar sizes were used for plaster and mortar testing in other buildings.

232 **OUT-OF-PLANE TEST SETUP**

233 The adopted test setup closely resembled that used to conduct laboratory testing as reported in
234 Derakhshan (2011), and Fig. 9 shows a typical in-situ test setup. The test setup consisted of a
235 backing plywood sheet with its timber supporting frame connected to the existing floor
236 diaphragm. For one-way spanning walls, the applied force was partially distributed on the wall
237 surface, with a commercial vinyl airbag (1100 mm \times 2100 mm) with a skin thickness of 0.25 mm
238 being positioned symmetrically against the wall surface as shown by the shaded area in Fig. 5.
239 For two-way spanning walls, three airbags were used symmetrically against the wall surface, and
240 the loaded area was approximately 70% (WH1), 80% (WH2), or 68% (WH3 and WH4) of the
241 total wall surface. A low airbag inflation rate was adopted so that each half cycle took
242 approximately 10 minutes to complete. The lateral pressure was controlled manually by
243 adjusting the air inlet, with a typical applied force history being shown in Fig. 10. Despite
244 recognition that a repeated semi-cyclic loading history can be less damaging than a reversed
245 cyclic load history, the loading pattern shown in Fig. 10 was adopted due to difficulties
246 associated with implementation of a test setup that allowed load reversals to be applied.

247

248 Out-of-plane reaction forces were transferred through either 4 (one-way spanning walls) or 6
249 (two-way spanning walls) 10-kN load cells from the backing frame to the supporting frame
250 connected to the floor, and special smooth steel plates covered with a film of grease (Fig. 9a;

251 bottom-left) were used underneath the plywood backing frame to minimize friction losses. Wall
252 displacements were measured using linearly variable differential transducers (LVDT) with
253 300 mm stroke length, and a high-speed data acquisition (DAQ) system with multiple channels
254 was used to record the test data.

255 **TESTING PROGRAM**

256 **As-built Tests**

257 Eight tests were collectively performed on five as-built one-way vertically spanning walls, with
258 three of the tests being conducted on walls with modified top supports (Table 3). The top support
259 details that originally existed or were introduced for the purpose of a comparative study are
260 summarised in Fig. 5. For example, test AH1-B was performed after wall testing with the
261 original SA support conditions (AH1-A) and then removing the steel anchors from the top
262 support details. Similarly, Test AT-B (Fig. 5f) was conducted after the as-built continuous top
263 wall support had developed cracks during test AT-A (Fig. 5e). Finally, Wall WT was first tested
264 (WT-A) using the as-built support conditions (CB in Table 3; see also Fig. 5g and 9a). The top
265 concrete beam was next cut from both wall sides (Fig. 5h) so that no arching action could
266 develop in the wall plane and the wall was re-tested by promoting a pinned support condition
267 (WT-B). Four two-way bending tests that were conducted on four two-way spanning walls
268 having as-built support conditions are also reported in Table 3.

269 **Tests on Retrofitted Walls**

270 After being tested in their as-built conditions (including tests with modified support details),
271 several walls were retrofitted by either NSM FRP or NSM TSB methods and re-tested.
272 Consistent with the loading pattern, the retrofit work was undertaken on one (tension) face of the

273 wall only, but for earthquake resistance the retrofit should be undertaken on both wall faces.
274 Table 4 lists the tests conducted on retrofitted walls and the details of the retrofit methods. Walls
275 AH1, AH3, AT, and WT were retrofitted using the NSM FRP technique, which involved the use
276 of one or two carbon FRP strips (see Table 4). The 15 mm wide \times 1.2 mm thick strip had a
277 Young's Modulus of 165 GPa and a mean tensile strength of 3100 MPa and was positioned into
278 a groove that was cut into the wall surface. The groove extended vertically from top to bottom
279 and was positioned at the wall centerline. Two part epoxy was used to bond the CFRP strip into
280 the masonry substrate. To ensure maximum bond area the groove was entirely filled with epoxy
281 prior to insertion of the CFRP strip. The groove was located on the non-loaded wall face, i.e. on
282 the wall face that was subject to tensile actions, and on one of the tested walls (AH1) strain
283 gauge transducers were mounted directly to the strip.

284

285 Details of the retrofit method undertaken on Wall AH2 are also reported in Table 4, with the
286 technique being similar to the NSM FRP procedure discussed above but involving a slightly
287 larger groove dimension, the use of a twisted steel bar instead of an FRP strip, and the use of a
288 cementitious grout instead of epoxy.

289 **TEST RESULTS**

290 In the one-way spanning as-built walls, a crack occurred at the wall base, and the walls
291 developed an approximately horizontal crack (Fig. 11a) at an intermediate height of βh above the
292 wall base, with β being on average 0.56. The intermediate height crack was horizontal in all
293 tests except test AH3-A, in which the crack crossed three brick courses. The cracking pattern in

294 this wall was attributed to a combination of the previously mentioned high-cement-content
295 retrofit plaster and relatively weak bricks (see Table 2 for brick compressive strength).

296

297 During the one-way spanning as-built tests a rocking mechanism was formed and walls were
298 subjected to post-cracking displacements. The maximum post-cracking mid-height lateral
299 displacement was limited for safety considerations to approximately 70% of the wall nominal
300 thickness. Significant crushing was observed in the lime-based plaster on the loaded surface of
301 walls in building AH, as shown in Fig. 11b, and the plaster was debonded from the wall surface
302 (Fig. 11c). Plaster cracking and debonding was also observed at the base of Wall WT on the
303 loaded wall face, despite the plaster being cement-based. The observation of plaster deterioration
304 or spalling from the wall surface in buildings AH and WT suggested that both lime-based and
305 cement-based plaster layers are prone to debonding, resulting in a decrease in the wall thickness
306 at pivot points.

307

308 Subsequent testing on retrofitted walls resulted in numerous new cracks being formed in the
309 vicinity of the inserted strip or steel bar, with the final crack pattern for one test being shown in
310 Figs. 11d.

311 **Walls in Building AH (with steel anchors)**

312 *AH1 and AH2 – As-built*

313 Fig. 12a shows that significant strength degradation occurred during test AH1-A. This reduction
314 in strength was partially attributed to the aforementioned plaster deterioration, which reduced the
315 moment arm of the restoring wall gravitational and inertial forces. The other factor that affected

316 the wall strength was weakening of the bond at the top support anchorages due to the large wall
317 rotations. At the conclusion of test AH1-A the wall had experienced 7 repeated semi-cycles of
318 large displacements, and the wall behavior reached an ultimate residual state. Steel anchors at the
319 top support were then unbolted and test AH1-B was conducted. The latter test showed that the
320 removal of the top anchors resulted in only a slight decrease in wall strength from the residual
321 strength recorded at the end of test AH1-A. It was concluded that the wall anchorage increased
322 the initial strength significantly by about 150% (0.5 kPa compared to 0.2 kPa, respectively for
323 post-cracking peak strength and the residual strength in Fig. 12a), but that this effect sharply
324 diminished during the repeated loading. Due to the inherent variability in this type of connection
325 and the vulnerability of the connection to cyclic loading, it is impractical to consider the
326 improved strength for assessment of walls with similar anchorage. However the installation of
327 anchors is recommended as they prevent the wall from responding in a cantilever mode. The
328 arching action that developed due to the top timber diaphragm support resulted in the residual
329 strength of AH1 exceeding that obtained from the trilinear model, as shown in Fig. 12b. In
330 contrast to the results for AH1, the trilinear model overestimated the strength of AH2 by about
331 15%. The cracking force of Wall AH2 was not captured during testing due to a test setup error,
332 and unlike AH1, this wall was tested with TD support conditions only. As AH1 and AH2 had the
333 same dimensions and were vertical strips of the same wall, the increased strength obtained in test
334 AH1-B was attributed to variability in masonry material properties and quality of construction.
335 This observation is consistent with a companion study by Lumantarna et al. (2013), which
336 reports COV of up to 50% for in-situ material tests. Consistent with the observed degradation of
337 plaster at the cracked joint, the trilinear force-displacement model was obtained assuming an

338 effective wall thickness which did not include the plaster layer. However, the weight of the
339 plaster layer was included in the calculations.

340

341 Correlation of the results from AH1-B and AH2-A with the lab-based model suggests that
342 arching action that developed due to the timber roof support resulted in less than 30%
343 improvement in wall strength. This additional strength is considered to be undependable when
344 undertaking a wall assessment, as the additional strength is developed only when the wall is
345 subjected to large lateral displacements.

346

347 *AH1 and AH2 – Retrofitted*

348 Walls AH1 and AH2 were retrofitted using, respectively, NSM FRP and NSM TSB techniques
349 and were then re-tested (see Table 4). Both retrofit schemes resulted in a substantial increase in
350 the wall stiffness, peak strength, and ductility capacity. Fig. 12c shows that unlike the as-built
351 walls, the retrofitted walls retained significant stiffness as the wall lateral displacement at crack
352 height increased up to nearly 80 mm (nearly 70% of wall nominal thickness). This absence of
353 strength loss with displacement results in significant ductility capacity. As detailed in Table 5,
354 the results of tests AH1-NSM FRP and AH2-NSM TSB showed improvement in the wall peak
355 strength by, respectively, 670% and 614% when compared to the as-built walls.

356

357 The failure mode in AH1-NSM FRP was in the form of numerous visible cracks that developed
358 within the vicinity of the CFRP strip, propagating from the wall centreline towards the top and
359 bottom wall edges. The development of masonry cracking led to gradual debonding of the CFRP

360 strip (see Fig. 13a for same failure mode for test WT-NSM FRP). Strip rupture, a brittle failure
361 mode associated with the NSM FRP strengthening technique, was not observed as the peak
362 measured stresses that developed in the strip were only 40% of that necessary to cause strip
363 rupture. The maximum strain measured in the CFRP strip during test AH1-NSM FRP was 7500
364 $\mu\epsilon$ (analogous to a tensile stress of 1240 MPa) compared to the CFRP manufacturer's suggested
365 maximum design tensile strength of 3100 MPa. The failure mode in AH2-NSM TSB was in the
366 form of local cracking of masonry and local bending of the TSB (Fig. 13c).

367

368 As summarised in Table 5, the results of both tests AH1-NSM FRP and AH2-NSM TSB suggest
369 that the residual displacement is significant (nearly 15 mm; 20% maximum displacement). This
370 observation suggests that although a URM wall strengthened using these techniques may satisfy
371 strength requirements at the ultimate limit state, the wall loses functionality after it has been
372 subject to large displacements.

373

374 *AH3 – As-built*

375 Fig. 12d shows the response of AH3, adjusted to exclude prior wall inelastic deformations. The
376 response of this wall was characterised by rocking and unrestrained vertical wall deformation
377 until the 25 mm gap (see Fig. 5g) was exceeded, after which arching action developed that
378 resulted in a nearly 100% increase in the wall strength. When discounting arching action, the
379 response of AH3 had good correlation with the trilinear model. Such a strength increase would
380 not occur during earthquake loading of out-of-plane walls as the full wall length will experience
381 comparable deformations and therefore the extent of boundary restraint present in this test would

382 not be provided in the real scenario. The main finding of this test was that the post-cracking
383 behavioral curve excluding arching action was in good agreement with the predictive model.
384 Similar to the case of AH1, moderate strength degradation occurred due to deterioration of the
385 lime-based plaster.

386

387 *AH3 – Retrofitted*

388 The NSM FRP retrofit method applied to wall AH3 led to improved wall peak strength of 440%
389 (see Table 5 and Fig 12e) when compared with the strength of the as-built wall (excluding the
390 increase in as-built wall strength due to arching action). The failure mode was in the form of a
391 sudden pull-out of the top portion of the CFRP strip (Fig. 13b), precluding ductile behavior.
392 Consequently, consideration should be given in seismic retrofit design to prevent this failure
393 mode. Similar to test AH1–NSM FRP no strip rupture was observed, and substantial cracking
394 occurred in the masonry wall in the vicinity of the FRP strip.

395 **Wall AT (continuous URM wall)**

396 *AT-As-built*

397 The strength of the one-way spanning wall AT was measured to be more than twice that obtained
398 from the lab-based trilinear model (4.5 kPa compared to 2.1 kPa in Fig. 12f) due to the fixity
399 provided by the continuous URM top support (see Fig. 5e). The effect of the applied overburden
400 on wall AT was included when calculating the predicted wall behavior using the analytical
401 method discussed earlier.

402

403 During test AT-A additional vertical, horizontal, and diagonal cracking occurred at the top
404 corners of the tested wall strip. Re-testing the wall (AT-B) showed that wall stiffness and
405 strength decreased, as reported in Fig. 12f. The curve representing test AT-B in Fig. 12f has been
406 adjusted to exclude the inelastic deformations (about 15 mm) that occurred during test AT-A.

407

408 *AT-Retrofitted*

409 Due to the increased strength of the as-built wall resulting from continuity at the top support,
410 from arching action, and from substantial additional axial load on the wall segment, the increase
411 in flexural strength as a result of the NSM FRP strengthening was not pronounced, being only
412 27% as detailed in Table 5. The wall ductility capacity improved, with almost no reduction in
413 wall strength as the wall displacement increased. However the wall exhibited 50 mm of residual
414 displacement, which was equal to more than 35% of the maximum wall displacement as detailed
415 in Table 5.

416 **Wall WT (CB top support)**

417 *WT - As-built*

418 A relatively stiff concrete beam that was cast above wall WT resulted in significant arching
419 action, such that wall WT remained uncracked during test WT-A. Subsequently the wall was re-
420 designated as WT-B and modified to have a pinned support condition that when re-tested
421 resulted in wall cracking at a 3.2 kPa face pressure (Fig. 12g). Wall WT-A sustained a face
422 pressure of more than 1.5 times the face pressure associated with wall cracking for WT-B when
423 the top support concrete ring was cut (4.9 kPa compared to 3.2 kPa from Fig. 12g). Fig. 12h

424 shows that the wall strength and the general shape of the behavioral curve dictating Δ_2 (see also
425 Fig. 2) had a good correlation with the lab-based idealised model. The measured initial cracked
426 wall stiffness was greater than the predicted equivalent, but as discussed previously the initial
427 stiffness has an insignificant effect on the adopted displacement-based wall assessment (Griffith
428 et al. 2003).

429

430 *WT-Retrofitted*

431 After being retrofitted, the strength of Wall WT-NSM FRP (5.6 kPa face pressure; see Fig. 12g)
432 was 75% greater than that of the unretrofitted wall (3.2 kPa face pressure at cracking), and as
433 detailed in Table 5, the improvement in wall strength due to the retrofit work was 830% when
434 compared to the as-built maximum post-cracking strength (0.6 kPa). The wall behavior was
435 ductile, and similar to the test on retrofitted wall AH1, the failure mode was characterized by
436 cracking in the masonry substrate and debonding of the strip (Fig. 13a). Similar to tests on
437 retrofitted walls AH1 and AH2, test WT-NSM FRP also resulted in a residual displacement in
438 excess of 20 mm (more than 20% wall maximum displacement).

439

440 Investigation of the data presented in Fig. 12g suggests that the out-of-plane strength of wall WT
441 with the as-built support details was approximately 1.2 times the seismic demand (NZS
442 1170.5:2004, NZS 2004) calculated for this wall configuration and site, being a region with high
443 seismicity (Wellington, New Zealand). These test data suggest that constructing a bond beam in
444 an existing building at the floor or roof levels is a reliable option for improving the out-of-plane

445 seismic wall response. Fig. 12g also suggests that when the top concrete beam is absent, the
446 same wall retrofitted using the NSM FRP technique meets the strength requirements for the
447 region discussed, although wall loading will result in substantial residual displacement.

448

449 Table 6 details the uncracked and cracked wall stiffness data measured during the tests
450 conducted on three one-way spanning walls and on the two-way spanning walls. The ratio of the
451 cracked wall stiffness to the measured uncracked equivalent was found to be on average 0.34,
452 but with large variation among the three walls (CoV=1.4). As a convention, a secant stiffness
453 corresponding to two-thirds of the wall maximum force resistance was calculated from the post-
454 cracking force-displacement curves and was assumed as the cracked wall stiffness. The ratio of
455 the maximum wall face pressure before cracking, w_{cr} , to the residual wall face pressure after
456 cracking, w_{max} , is notably high for several one-way spanning walls (see Table 6). This ratio
457 varies from 250% to 530%, with the average value being 353%. This relatively high average
458 percentage suggests that a study to show whether strength-based criteria for wall seismic
459 assessment are more efficient compared to stability-based criteria is worthwhile, particularly for
460 walls that have strong plaster finish and are located in regions with low seismicity.

461 **Two-way spanning walls**

462 Fig. 14a and Fig. 14b show the results of two-way spanning tests performed on damaged walls
463 WH1 and WH2. Both walls underwent small amounts of inelastic deformation (approx. 0.5 mm,
464 nearly 20% wall maximum displacement), with only minor additional cracking being developed.

465

466 Analysis of the response envelope shown in Fig. 14b indicated that at a face pressure of
467 approximately 3.2 kPa the wall stiffness reduced by approximately 65% from 3.6 kPa/mm to
468 1.2 kPa/mm. This reduction in the wall stiffness was due to extension of the crack pattern as
469 shown in Fig. 6. In contrast, WH1 maintained the same stiffness during testing, suggesting that
470 the existing cracks did not open sufficiently to cause deterioration of wall stiffness. As discussed
471 previously, the existing cracking in WH1 was not as extensive as that shown in Fig. 6 for WH2.
472 The retrofit of WH2 using two strips of NSM FRP resulted in a 67% improvement in the wall
473 stiffness, from 1.2 kPa/mm (WH2) to 2 kPa/mm (WH2-NSM FRP). Because the wall stiffness
474 had improved and the wall resistance exceeded that required as per the NZ seismic loading
475 requirements for regions with high seismicity, the test was terminated to avoid further wall
476 damage. It should be noted that from the results of tests on the other retrofitted walls, the NSM
477 retrofit method does not substantially improve wall stiffness, but instead the method significantly
478 improves wall strength. The true effectiveness of the retrofit deployed for this strengthened two-
479 way spanning wall could not be assessed due to the applied forces being insufficient to cause
480 wall failure.

481
482 Fig. 15 shows a comparison between the force-displacement plots of unretrofitted wall WH3 and
483 retrofitted wall WH4. Although the walls had identical dimensions and were merely located in
484 different rooms, the flexural stiffness of WH4 (retrofitted) was 54% that of WH3 (as-built).
485 Therefore the effectiveness of the retrofit work could not be established due to possible variation
486 in material properties, construction details, e.g. the plaster thickness on each side, and due to
487 potentially different extents of non-visible damage.

488

489 The measured wall stiffness during the tests on pre-cracked walls WH1 and WH2 was on
490 average 2.9 kPa/mm, as detailed in Table 6. The measured wall stiffness during the tests on
491 uncracked partition walls WH3 and WH4 was much higher than the measured value for the pre-
492 cracked walls, despite the uncracked walls having larger wall dimensions. The average
493 uncracked wall stiffness was 14.6 kPa, which was approximately 5 times greater than the average
494 stiffness of the pre-cracked walls (2.9 kPa). This difference was attributed to two factors, one
495 being prior cracking and the other being the unrestrained top horizontal edge in wall tests WH1
496 and WH2.

497

498 Although both walls WH1 and WH2 were pre-cracked, the maximum applied face pressure was
499 approximately 30 times higher than that expected for a one-way spanning wall with the same
500 thickness (calculated as 0.2 kPa using the procedure described in NZSEE (2006)). This
501 comparison suggests that unnecessary retrofit measures can be avoided by utilising in-situ tests
502 (C7.2.3.3.4 of ASCE 2007), although variability in wall stiffness, as shown in Fig. 15, should
503 also be considered. Due to the substantial cost of conducting in-situ tests, this type of evaluation
504 (including the required study into the variability of the results) is usually beneficial only when a
505 large number of comparable walls exist in a masonry building.

506 **SUMMARY AND CONCLUSIONS**

507 A report of in-situ out-of-plane airbag testing that was conducted on as-built and retrofitted URM
508 walls of four different buildings was presented. The test walls had plastered surfaces, and
509 included one-way vertically spanning walls and uncracked or pre-cracked two-way spanning

510 walls. The experimental program included testing the same walls with original and modified top
511 support types.

512

513 A concrete ring beam positioned above URM bearing walls significantly increased wall strength
514 and prevented excessive wall displacements. It was suggested that constructing bond beams at
515 the floor or roof level of URM bearing wall buildings is a reliable seismic improvement option.

516

517 A single CFRP NSM strip or two inserted TSBs substantially increased the post-cracking out-of-
518 plane flexural strength of one-way spanning walls AH1, AH2, AH3, AT, and WT by,
519 respectively, 670%, 614%, 440%, 27%, and 830%. These increases in the wall strength were
520 accompanied by residual displacements from nearly 20% and up to 35% of the wall maximum
521 displacement. Therefore these retrofit techniques are recommended for ultimate limit state design
522 where the functionality of the wall after a design earthquake is of limited importance. The
523 behavior of a retrofitted wall that failed due to NSM FRP strip pull-out was brittle, but
524 significant ductility was observed for walls where the NSM strip debonding failure mode was
525 initiated. Consideration should be given in the NSM FRP seismic retrofit design to prevent the
526 pull-out failure mode.

527

528 A previously cracked two-way spanning wall was tested in both as-built and NSM FRP
529 retrofitted conditions. The retrofit work improved the wall stiffness by 67%. No apparent
530 improvement was observed when the stiffness of a retrofitted two-way spanning wall was
531 compared to a different unretrofitted wall, potentially due to differences in the wall construction

532 and/or different extents of prior non-visible wall damage. The complete effectiveness of the
533 retrofit scheme for two-way walls could not be assessed due to the applied forces being
534 insufficient to promote wall failure. It is also suggested based on this variability that individual
535 wall boundary conditions, material properties, and previous loading history are required to be
536 studied before a general seismic assessment procedure can be used.

537

538 The tested two-way spanning walls had strengths that were significantly greater than that
539 calculated for a one-way spanning wall with the same thickness, but their out-of-plane stiffness
540 was shown to be significantly reduced (by a factor of 5) due to cracking and/or due to the top
541 wall edge being unrestrained. Irrespective of the results of wall assessment using procedures
542 based on a one-way bending idealisation, even pre-cracked two-way spanning walls may satisfy
543 current seismic loading standards. This study highlighted the merits of conducting in-situ testing
544 as recommended by ASCE (2007) to assess wall strength, especially when a large number of
545 comparable walls are involved and a desktop evaluation can potentially impose substantial
546 unnecessary retrofit measures to be implemented in buildings. Significant variability was
547 observed in the measured stiffness of two-way spanning walls of a single building, suggesting
548 that multiple walls should be tested when a building is to be assessed by means of in-situ testing.

549 **ACKNOWLEDGEMENTS**

550 The authors wish to acknowledge the financial support provided by the New Zealand
551 Government via the Foundation for Research Science and Technology (FRST). The authors also
552 wish to acknowledge the financial support provided by the Australian Research Council (ARC).

553

554 REFERENCES

555 Abrams, D. P., Angel, R., Uzarski, J. (1996). "Out-of-plane strength of unreinforced masonry
556 infill panels," *Earthquake Spectra*, EERI, 12(4):825-844.

557

558 ASCE (2007). *Seismic Rehabilitation of Existing Buildings*, ASCE/SEI 41-06. American
559 Society of Civil Engineers, Reston, VA.

560

561 ASTM (2001). "Standard test method for measurement of masonry flexural bond strength." C
562 1072 00a. ASTM International, Pennsylvania, United States.

563

564 ASTM. (2003). "Standard Test Methods for Sampling and Testing Brick and Structural Clay
565 Tile." C 67-03a, ASTM International, Pennsylvania, United States.

566

567 ASTM (2004). "Standard test method for compressive strength of masonry prisms." C 1314 03b.
568 ASTM International, Pennsylvania, United States.

569

570 Calvi, G. M., Kingsley, G. R., and Magenes, G. (1996). "Testing of masonry structures for
571 seismic assessment." *Earthquake Spectra*, 12(1), 145–162.

572 Carpinteri, A., Invernizzi, S., and Lacidogna, G. (2005). "In situ damage assessment and
573 nonlinear modelling of a historical masonry tower." *Engineering Structures*, 27(3), 387–395.

574

575 Chiostrini, S., Galano, L., and Vignoli, A. (2003). "In situ shear and compression tests in ancient
576 stone masonry walls of Tuscany, Italy." *Journal of Testing and Evaluation*, 31(4), 289–303.
577

578 Corradi, M., Borri, A., and Vignoli, A. (2003). "Experimental study on the determination of
579 strength of masonry walls." *Construction and Building Materials*, 17(5), 325–337.
580

581 Derakhshan, H. (2012). "Seismic assessment of out-of-plane loaded unreinforced masonry
582 walls" PhD thesis, Faculty of Engineering of The University of Auckland, New Zealand.
583

584 Derakhshan, H., Griffith, M., and Ingham, J. (2013). "Out-of-plane behavior of one-way
585 unreinforced masonry walls.", *ASCE Journal of Engineering Mechanics*, 139, 4, 409-417.
586

587 Downes, G., Dowrick, D., Van Dissen, R., Taber, J., Hancox, G., & Smith, E., (2001). The 1942
588 Wairarapa, New Zealand, earthquakes; analysis of observational and instrumental data, *Bull. of*
589 *the N.Z. Soc. for Earthquake Engineering*, 34, 125-157.
590

591 Doherty, K. T. (2000). "An investigation of the weak links in the seismic load path of
592 unreinforced masonry buildings," PhD thesis, Faculty of Engineering of The University of
593 Adelaide, Australia.
594

595 Griffith, M. C., Magenes, G., Melis, G., and Picchi, L. (2003). Evaluation of out-of-plane
596 stability of unreinforced masonry walls subjected to seismic excitation. *Journal of Earthquake*
597 *Engineering*, 7(SPEC. 1):141–169.

598

599 Griffith, M.C. , Kashyap, J. , Mohamed Ali, M.S. (2013). Flexural displacement response of
600 NSM FRP retrofitted masonry walls. Article in Press (DOI: 10.1016/j.conbuildmat.2012.06.065).

601

602 Hamed, E., Rabinovitch, O. (2010). Failure characteristics of FRP-strengthened masonry walls
603 under out-of-plane loads. *Engineering Structures*, 32(8): 2134-2145.

604

605 Kashyap, J., Willis, C.R., Griffith, M.C. , Ingham, J.M., Masia, M.J. (2012). Debonding
606 resistance of FRP-to-clay brick masonry joints. *Engineering Structures*, 41: 186-198.

607

608 Lumantarna, R., Biggs, D. T., and Ingham, J. M. (2013). "Compressive, Flexural Bond and Shear
609 Bond Strengths of In-Situ New Zealand Unreinforced Clay Brick Masonry Constructed Using
610 Lime Mortar between the 1880s and 1940s." *J. Mater. Civ. Eng.*, 10.1061/(ASCE) MT.1943-
611 5533.0000685 (Sep. 18, 2012).

612

613 NZSEE (2006). "Assessment and Improvement of the Structural Performance of Buildings in
614 Earthquake. Recommendations of a New Zealand Society for Earthquake Engineering Study
615 Group on Earthquake Risk Buildings". Wellington, New Zealand.

616

617 Priestley, M. J. N. (1985). "Seismic behavior of unreinforced masonry walls." *Bulletin of the*
618 *New Zealand National Society for Earthquake Engineering*, 18(2), 191–205.

619

620 Vaculik, J. (2012) *Unreinforced Masonry Walls Subjected to Out-of-Plane Seismic Actions*. PhD
621 Thesis, University of Adelaide.

622

623

624

625 LIST OF TABLES

626 TABLE 1: Wall properties

627 TABLE 2: Material properties

628 TABLE 3: In-situ as-built testing program

629 TABLE 4: In-situ retrofitted wall testing program

630 TABLE 5: In-situ retrofitted wall test results

631 TABLE 6: In-situ as-built test results

632 TABLES

633

TABLE 1: Wall properties

Wall	Test span condition	Thickness ¹	Height	Length	Plaster ² thickness		Masonry unit dimensions (mm)
		t_n (mm)	h (mm)	l (mm)	t_{p1} (mm) ³	t_{p2} (mm) ⁴	
AH1	One-way	150	3300	1170	20 ⁵	20 ⁵	68 × 230 × 112
AH2	One-way	150	3300	1170	20 ⁵	20 ⁵	
AH3	One-way	270	2700	1200	20 ⁵	10	
AT	One-way	240	3000	1200	---	10	75 × 220 × 105
WT	One-way	255	4000	1250	15	15	75 × 220 × 105
WH1	Two-way	130	2730	3850	15	15	160 × 300 × 95
WH2	Two-way	130	2730	3480	15	15	
WH3	Two-way	130	2940	4100	15	15	
WH4	Two-way	130	2940	4100	15	15	

Notes - (1) Including plaster (2) Cement-based plaster unless indicated otherwise
(3) Loaded wall face (4) Other wall face (5) Lime-based plaster

634

635

TABLE 2: Material properties

	Half-brick compressive strength, f_b' (MPa) ASTM C67-03a (ASTM 2003)	Mortar compressive strength, f_j' (MPa)	Masonry compressive strength, f_m' (MPa) ASTM C 1314-03b (ASTM 2004)	Plaster compressive strength, f_p' (MPa)	Masonry flexural bond strength, f_{ib}' (MPa) C 1072 00a ASTM (2001)
Bldg	(No. of samples) Mean (CoV)				
AH	(7) 8.8 (0.19)	(8) 3.3 (0.37)	(5) 3.2 (0.2)	(9) 1.4 (0.37)	(9) 0.04 (0.5)
AT	(9) 19.4 (0.16)	(9) 5.7 (0.28)	(6) 9.6 (0.28)	N/A	N/A
WT	(5) 25.9 (0.25)	(6) 17.7 (0.46)	(5) 9.7 (0.18)	N/A	(2) 0.61 (N/A)
WH	(3) 32* (0.26)	N/A	(4) 13.8* (0.5)	(7) 3.4 (0.15)	N/A

637 * Compressive strength results are based on net block area

TABLE 3: In-situ as-built testing program

Wall	Span Condition	Test	Wall support		
			Top	Bottom	Conditions
AH1	One-way	A	SA	Ground	O
	One-way	B	TD	Ground	M
AH2	One-way	A	TD	Ground	M
AH3	One-way	A	G	Ground	M
AT	One-way	A	C	C	O
	One-way	B	CC	C	M
WT	One-way	A	CB	Ground	O
	One-way	B	TD	Ground	M
WH1	Two-way	A	U	CB	O
WH2	Two-way	A	U	CB	O
WH3	Two-way	A	CB	CB	O
WH4	Two-way	A	CB	CB	R

Notes - O: Original; M: Modified; C: Continuous; TD: Timber Diaphragm
 CC: Cracked Continuous; CB: Concrete Beam; SA: Steel Anchor; G: Gap;
 U: Unrestrained, R: Retrofitted

641

TABLE 4: In-situ retrofitted wall testing program

Test	d_f (mm)	b_f (mm)	b_p (mm)	t_p or d_b (mm)	# of NSM Bar/strip	S_v (mm)
AH1-NSM FRP	35	8	15	1.2	1	1170
AH2-NSM TSB	30	10	---	6	2	585
AH3-NSM FRP	25	6	15	1.2	1	1200
AT-NSM FRP	25	6	15	1.2	1	1200
WT-NSM FRP	20	6	15	1.2	1	1250
WH2-NSM FRP	30	5	15	1.2	2	1200
WH4-NSM FRP	30	5	15	1.2	2	1200

642 d_f = width of groove; b_f = depth of groove; b_p = width of FRP strip; t_p = thickness of FRP strip;643 d_b = outer diameter of TSB; and S_v = centre to centre spacing of vertical bars/strips

644

645

646

TABLE 5: In-situ retrofitted wall test results

Wall	Post cracking as-built face pressure (kPa)	Retrofitted maximum achieved face pressure (kPa)	Retrofit strength improvement (%)	Residual disp. as a percentage of max. disp. (%)
AH1	0.18	1.4	670	20
AH2	0.14	1.0	614	20
AH3	0.90	4.9	440	---**
AT	4.10	5.2	27	35
WT	0.60	5.6	830	20
WH2	4.90	5.9	N/A*	20
WH4	3.80	3.80	N/A*	---***

647 * The true effectiveness of the retrofit is not evident due to test termination; ** brittle failure; *** elastic behavior

648

649


650

TABLE 6: In-situ as-built test results

Test	K_{uc}	K_{cr}	K_{cr}/K_{uc}	w_{cr} (kPa)	w_{max} (kPa)	$w_{cr}/w_{max} \times 100$ (%)
	(kPa/mm)					
<u>One-way walls</u>						
AH1-A	0.43	0.02	0.05	0.5	0.2	250
AH3-A	0.64	0.56	0.88	2.5	0.9	280
WT-B	1.3	0.12	0.09	3.2	0.6	530
Average (CoV)			0.34 (1.4)			353 (0.4)
<u>Two way walls</u>						
WH1-A		2.3				
WH2-A		3.5				
WH3-A	18.9					
WH4-A	10.3					
Average		14.6	2.9			

651


652



(a) Steel anchors in demolished wall



(b) Anchorage details



(c) Anchorage sketch

Fig. 1: Grouted steel anchors (SA)




Figure 2: Wall out-of-plane behaviour

654



Fig. 3: Case study buildings

655



(a) AH (b) AT and WT (c) WH

Fig. 4: Typical wall cross section

656





Fig. 5: Dimensions and boundary conditions of one-way vertically spanning walls; thick black lines indicate wall cracks; shaded area indicates the position of airbags; refer to Table 3 for details of boundary support codes

657



658 Fig. 6: Wall WH2 initial crack pattern and crack extension (dashed)



(a) Wall cross section



(b) Wall disintegration

Fig. 7: Scarcity of header bricks in a two-leaf wall

659




(a) Masonry prism testing



(b) Four-point bending test

Fig. 8: Material testing on building WH

660



(a) Test setup diagram for WT-A; inset: top support details for other walls



(b) Actual setup (WT-A)

661

Figure 9: Typical in-field test setup details




Fig. 10: Recorded loading history (from test WH2)

662



663

Fig. 11: Wall cracking and deterioration of plaster





FIG. 12: Face pressure-lateral displacement relationship-Contd.




FIG. 12: Face pressure-lateral displacement relationship



(a) Strip debonding
(WT – NSM FRP)




(b) Strip pull-out
(AH3 – NSM FRP)




(c) Local bending of a TSB (AH2 –
NSM TSB)

Fig. 13: Failure modes in retrofitted walls

666



(a) Test WH1-A



(b) Tests WH2-A and WH2-NSM FRP

FIG. 14: Results of tests on WH1 and WH2

667




Fig. 15: Results of tests on WH3 and WH4

668